


**MAP UNIT**

**Seddor very gentle slopes**

**MAP SYMBOL SVG**



**GENERAL DESCRIPTION**

Very gentle lower slopes (1-3%) on sedimentary down wash from the ridge country. In general the unit has deep yellow duplex soils with moderate shrink-swell potential.

**LAND ASSESSMENT**

- A Erosion Risk with Land Disturbance
  - Class 2 Gentle short slopes
- B Constraints on Construction
  - Class 2 Moderate shrink-swell potential
- C Effluent Disposal by Soil Absorption
  - Class 3(4) Slow percolation rates (low permeability clay)
- D Small Farm Dams
  - Class 1

**OVERALL ASSESSMENT FOR RURAL SUBDIVISION 2-10 ha (Considering A, B, C & D)**

- Class 2 Requires effluent disposal tests